





## **Application for Cutback Parking**

Cut-back parking refers to space taken from the pedestrian realm on a street and dedicated to parking or related uses (see image, right). City ordinance requires that all cut-back parking requests be approved by the City Traffic Engineer, and that HPW staff notify the district council member and all at-large councilmembers of any approval or denial of cut-back parking. Approval of cutback parking does not grant the right to reserve the parking for private use.



Cut-back parking reduces the amount of ROW available for the pedestrian realm (the publicly-available space outside the roadway). The image below defines the minimum widths for pedestrian realm elements.



		Min Width (ft) <sup>1</sup>
1	Frontage Buffer	1
2	Sidewalk	5 <sup>2</sup>
3	Safety Buffer	4

1-Absolute minimum. Wider is desirable.

2-Sidewalk width depends on street type. See IDM-Ch17 for more info.

## Cutback parking **will not** be approved if:

- Any of the pedestrian realm elements do not meet the minimum values
- An existing drainage ditch would be covered without approved drainage compensation
- Overall available on-street parking is reduced
- Any safety concerns are identified related to the cutback parking

## Cutback parking **may** be approved if:

- No on-street parking is currently provided along the street
- There are specific safety concerns identified if the cutback parking is NOT provided
- There is a specific need for the cutback parking that cannot be satisfied by any other on- or off-site location.





To proceed with the application, please fill in the relevant information below, and send the form with a proposed sketch/schematic of the cut-back parking to <a href="mailto:safestreets@houstontx.gov">safestreets@houstontx.gov</a> or your existing contact. The <a href="mailto:sketch/schematic must show all dimensions of the cut-back parking and pedestrian realmassidentified">safestreets@houstontx.gov</a> or your existing contact. The <a href="mailto:sketch/schematic must show all dimensions of the cut-back parking and pedestrian realmassidentified">safestreets@houstontx.gov</a> or your existing contact. The <a href="mailto:sketch/schematic must show all dimensions of the cut-back parking and pedestrian realmassidentified">safestreets@houstontx.gov</a> or your existing contact. The <a href="mailto:sketch/schematic must show all dimensions of the cut-back parking and pedestrian realmassidentified">safestreets@houstontx.gov</a> or your existing contact. The <a href="mailto:sketch/schematic must show all dimensions of the cut-back parking and pedestrian realmassidentified">sketch/schematic must show all dimensions of the cut-back parking and pedestrian realmassidentified</a> on the reverse side.

Requestor Contact Information	
Name of development (if applicable)	
Name of street	
Adjacent cross streets	
Justification for Cutback request	
Width of street (ft) (curb to curb, or edge of pavement to edge of pavement)	
Street right-of-way (ft)	
Description of existing/proposed drainage	